



BRASIL
BOLSA
BALCÃO



B3 Week – New CO-LO Network Design

2024

Ricardo Geraldini – *IT Associate Director*
Eduardo Kashiwakura – *DC/COLO Manager*
Adeilson Rateiro – *Network Architect, CCIE*
Marcio Ianni – *Network Engineer*




AGENDA

- 1. Scope of Network Modernization**
- 2. Drivers for Changes**
- 3. Project Timeline**
- 4. Design Overview, Performance & Observability**
- 5. DC Cabling**
- 6. Simulation Phase**
- 7. Networking Migration Overview – MD & OE**




[B]³

SCOPE OF NETWORK MODERNIZATION



[B]³ Scope of Network Modernization


Binary MD vs OE:
 DRV: MD +90% Faster
 EQT: MD +80% Faster




⊗ Switch/Network
 □ Application
 (X, Y) #Instances, #Serves
 (n) #Network components

[B]³

DRIVERS FOR CHANGES



[B]³ Understanding the drivers for changes



Network device end-of-life cycle

- Good opportunity to rethink our COLO access network design



Architecture Update (*Requirements*)

- Improve determinism and fairness
- More network simplicity for management
- Increase network visibility
- Reduce multiplicity
- No interference between OE and MD flows



Discussions & Initiatives

- Discussions with vendors and *some* market participants
 - Multicast and Unicast routing designs
 - Device models and behaviors
 - Forwarding modes and Overtaking Probability
 - Cable length normalization
- Extensive lab validation (*BR, US & UK*)



Trade-Offs & Final Decision


- MD Dedicated Network – All layers with Nexus 3550T
- OE Dedicated Network – Edge layer with Nexus 3548XL
 - Only cut-through is supported
 - Other models have port preference
 - Other vendors are off the table due to the lack specialized support and skilled professionals in Br
 - Network policies and rules are being studied and will be published on Q4/2024

[B]³

PROJECT TIMELINE



[B]³ Project Macro Timeline







NETWORK DESIGN OVERVIEW **PERFORMANCE & OBSERVABILITY**

[B]³ New Network Design

ORDER ENTRY UNICAST NETWORK






MARKET DATA MULTICAST NETWORK



[B]³ Network Performance Comparison


MARKET DATA

ORDER ENTRY


	CURRENT	NEW	CURRENT	NEW
 Latency Path	~11us <i>One-Way</i>	~800ns <i>One-Way</i>	~22us <i>RTT</i>	~4us <i>RTT</i>
 Port-2-Port Variance	Not Measured	~1ns	Not Applied	Not Applied
 Overtaking Probability	Not Applied	Not Applied	Not Measured	Up to ~4ns <i>No more above</i>

[B]³

Network Observability (TAPs & Timestamping)



[B]³ Network Observability (TAPs & Timestamping)



[B]³


NETWORKING INFRA

DC CABLING




[B]³ Cabling Infrastructure (per half rack)

Current Network



**2x Connections (Primary and Secondary) both used for Market Data and Order Entry

Binary/25




Unicast and Multicast Split

**2x Connections (Primary and Secondary) for Market Data.


**2x Connections (Primary and Secondary) for Order Entry.

[B]³ Simulation Environment (per half rack)

Binary/25



Customer rack's patchpanel



After migration phase the current network will be deactivated

[B]³


NETWORKING TESTS

SIMULATION PHASE



[B]³ Simulation Environment Overview

- ✓ **Expansion of participant's switch and/or port required for Q2/2025**
- ✓ The **Simulation Test Phase** will last for **about 3 months**
- ✓ **New and exclusive IP addressing**, and multicast groups will be used to **avoid interference** with the current production
- ✓ All **simulation tests** will **not interfere** with the **real production** environment
- ✓ New links will **receive FEEDS** (*with delay*) and connectivity to **simulation gateways**
- ✓ **All service IP addresses** will be **deactivated** after the Simulation Test Phase
- ✓ **Only links** and their **IPs** will be **reused** for the next phase (*Migration*)






NETWORK MIGRATION OVERVIEW – MD & OE




[B]³ Market Data Migration

- ✓ **All links** will be the **same** as simulation phase
- ✓ **MD** will be the **first migrated** service
- ✓ Will be **migrated in tranches**, in Q3/2025;
- ✓ Same **IP addressing**, and multicast groups as current production
- ✓ **All MD services** (*Bin / Fix*) will be **available** on the new MD network
- ✓ With **MD** already **migrated**, **OE** will continue to **operate via** the **legacy network**



[B]³ Order Entry Migration

- ✓ **All links** will be the **same** as simulation phase
- ✓ **OE** will be the **last migrated** service
- ✓ Will be **migrated in tranches**, in Q3/2025;
- ✓ Same **IP addressing** as in the current production environment
- ✓ **All OE services** (*Bin / Fix*) will be **available** on the new OE network
- ✓ With **all migration completed**, the **LEGACY** network will be **decommissioned**
- ✓ Full **services running** on the **new infrastructure**



[B]³ Wrap-up & Takeaways

- ✓ **Network architecture change:** Market Data and OE flows will be segregated over dedicated network
 - Cut-through as forwarding mode at the edge for OE Switches;
- ✓ **Participant's switch and/or port expansion required for Q2/2025** for the Simulation test phase;
- ✓ **3 months** of duration for the **Simulation Test Phase**;
- ✓ **MD and OE** will be **migrated in tranches**, in Q3/2025;
- ✓ **New network observability** will be available **Only for B3 internal use**;
- ✓ **New network policy and rules of engagement** is under construction and will be available in Q4 / 2024;
- ✓ **Technical deep-dive workshop** scheduled for **next week**;
- ✓ **B3 Technical team available for bi-lateral meetings.**



BRASIL
BOLSA
BALCÃO

THANK YOU!